



Ian Johnstone
DuPage County Facilities Management
421 N County Farm Road | Wheaton, IL 60187

July 28, 2025

RE: CO1 Auditorium Roof Photovoltaic System Installation

Page 1 of 3
Dear Ian:

Huen Electric, Inc. is pleased to provide the following quotation for above referenced project. This change order is based on drawing E105 of the bid package drawings received on May 14, 2025. It is subject to the following scope of work.

TOTAL.....\$ 224,183.00

(This Proposal is valid for 45 days)

Respectfully,
Huen Electric, Inc.

Signature on File

Ron Baker
Senior Project Manager

RE: CO1 Auditorium Roof Photovoltaic System Installation

Page 2 of 3

SCOPE OF WORK

INCLUSIONS

- I. PV System
 - A. Modules
 - 1. Furnish and install (153) Eagle 72HM G2 modules per layout on E105.
 - a. Part # JKM415M-72HL-V.
 - b. Furnish and install Eco-Foot 5D racking.
 - B. Inverters
 - 1. Furnish and install (2) Solar Edge 40KW Inverters
 - a. Part # SE40KUS (USE-SIN-USR0IBNS6)
 - b. Inverters to mount on inverter stand installed under the base bid.
 - C. PV Wiring
 - 1. Furnish and install (4) strings of #10 1000V PV wiring between the modules and inverters.
 - 2. Per conversation PV conduit to be installed exposed on the outside of the building to limit penetration.
 - D. Grounding
 - 1. Ground modules to grounding system at the north upper roof array.
- II. AC System
 - A. Furnish and install (2) 60A/3P breaker in the AC combiner distribution panelboard.
 - 1. The AC combiner distribution panel is located on the existing clerestory wall.
 - 2. Installation of the distribution panelboard is under the base bid.
 - B. Furnish and install AC conduit and cables between the inverters and the distribution panel.
- III. Testing & Commissioning
 - A. Testing and commissioning to follow guidelines as specified in the solar photovoltaic System 48 14 00 – 14 section 3.5 of the project manual.
 - B. Testing and commissioning of the lower roof array shall occur simultaneously with the upper roof.

RE: CO1 Auditorium Roof Photovoltaic System Installation

Page 3 of 3

CLAIFICATIONS

- I. Base bid includes North lower roof AC combiner distribution panelboard.
- II. Grounding of the lower array to utilize the upper array grounding system.
- III. Work shall be performed during normal operating hours.
- IV. This proposal expires after (15) days.

EXCLUSIONS

- I. Roof modifications or repair.
- II. Premium, Overtime or Holiday.
- III. Engineering fees
- IV. Basic material submittals.
- V. Downtime caused by others.
- VI. Dumpster
- VII. Porta John

We reserve the right to correct this quote for errors and omissions. Any additional cost or schedule impact and/or any unforeseen conditions that might arise as the result of the above change will be submitted on a time and material basis.