



Rack ' M Up Equipment Distributors

808 N Central Ave
 Ste D
 Wood Dale, IL 60191

Proposal

Proposal Date: 7/24/2023
Proposal #: 442
Project:

Bill To:

DuPage County Vehicle Maintenance
 421 N. County Farm Road
 Whaton, Illinois 60187

Description	Est. Hours/Qty.	Rate	Total
Scope -. Rack' M Up to provide; Installation of Mohawk vertical rise vehicle lift, project management, modifying concrete, and electrical connection. Union labor or prevailing wage will apply. All equipment and materials to be supplied by Rack' M Up or its subcontractors, necessary for proper installation. Excludes any permits fees or other special licenses. Excludes any additional insurance beyond what is currently carried. Certificate of Insurance is available and can be provided upon order and request.			
Install Mohawk Vertical Rise	1	15,900.00	15,900.00
Thermal scanning of floor prior to any concrete work to scan for in floor heat tubes or other mechanicals - must be done prior to any concrete work.	1	3,245.00	3,245.00T
Sawcut and remove old concrete	1	60,225.00	60,225.00
Furnish and Install Steel Reinforcement			
Dowels into existing slab			
Extend Existing Pit Width			
Slab Patch			
Note: No drawings have been made available - quote is based on not having to contend with any drains or other in floor obstacles not visible on site visit. Thermal Scanning of floor is not a 100% guarantee that any in floor heat or obstacles will be damaged. All due diligence and care will taken to avoid such issues however, Rack' M Up or any of its subcontractors will not be held responsible in the event such obstacle are damaged except due to negligence.			
Sub Contract Electrical	1	16,225.00	16,225.00T
remove existing lift and dispose - lift will have to be cut into sections with cutting torch, loaded onto to trailers and removed for proper disposal. Hydraulic oil to be disposed of in customers waste oil tank.	1	11,440.00	11,440.00
Total			\$107,035.00