



Rack ' M Up Equipment Distributors

Ste D
Wood Dale, IL 60191

Proposal

Proposal Date: 2/7/2024

Proposal #: 1114

Project:

Bill To:

DuPage County Vehicle Maintenance
421 N. County Farm Road
Whaton, Illinois 60187

Description	Est. Hours/Qty.	Rate	Total
<p>Scope -. Rack' M Up to provide; Installation of Mohawk vertical rise vehicle lift, project management, modifying concrete, and electrical connection. Union labor or prevailing wage will apply. All equipment and materials to be supplied by Rack' M Up or its subcontractors, necessary for proper installation operation. Excludes any permits fees or other special licenses. Excludes any additional insurance beyond what is currently carried. Certificate of Insurance is available and can be provided upon order and request.</p> <p>Lift Installation Receive and Install Mohawk Vertical Rise Heavy Duty Vehicle Lifts</p> <ul style="list-style-type: none"> • Prevailing wage Labor to be on site to receive and off load lifts • Installation of lifts to the point they are tested, approved and certified as operational • provide material - hydraulic fluid, anchors etc.. • provide all necessary equipment to offload and install lifts • project management of the job - including concrete, electrical and in floor heat repairs. - coordinate with the fleet manager <ul style="list-style-type: none"> • Installation labor is warranted for 1 year from date of acceptance - lifts are covered under the manufacturers warranty. • Follow Up - 30 day follow up visit to check over lifts and make any necessary adjustments - including checking on anchors, fluid, equalized, (level lifting). 	7	17,708.57143	123,960.00
Total			



Rack ' M Up Equipment Distributors

Ste D
Wood Dale, IL 60191

Proposal

Proposal Date: 2/7/2024

Proposal #: 1114

Project:

Bill To:

DuPage County Vehicle Maintenance
421 N. County Farm Road
Whaton, Illinois 60187

Description	Est. Hours/Qty.	Rate	Total
Sub Contract Concrete • Sawcut, remove, and dispose of old concrete • Furnish and Install Steel Reinforcement • Dowels into existing slab • Extend Existing Pit Width • Slab Patch Note: No drawings have been made available - quote is based on not having to contend with any drains or other in floor obstacles not visible on site visit.	7	58,571.42857	410,000.00
Total			



Rack ' M Up Equipment Distributors

Ste D
Wood Dale, IL 60191

Proposal

Proposal Date: 2/7/2024

Proposal #: 1114

Project:

Bill To:

DuPage County Vehicle Maintenance
421 N. County Farm Road
Whaton, Illinois 60187

Description	Est. Hours/Qty.	Rate	Total
Sub Contract Mechanical - In Floor Heat - <ul style="list-style-type: none"> • Thermal scanning of floor prior to any concrete work to scan for in floor heat tubes or other mechanicals - must be done prior to any concrete work. - performed 2/2/24 • Layout & mark the floor via thermal image gun to indicate location of existing in-floor radiant heat pipe • Provide and send a water sample test. • Drain and blow out the entire radiant system. • Furnish/install ProPEZ fittings to repair pipe for all 8 bays. We require a min. of 6" around the pipe to make a proper repair. • Pressure test each individual system after repair is made • Assist in maintaining pressure test verification while concrete is poured (assumes 2 bays are being poured at a time) • Fill, flush, and vent all systems. Upon heating hot water verification, we will put the system back to proper glycol mixture. We are assuming a 40% volume. • Provide (1) day of service check out and operation verification. • Mobilize material and tools to job site • Safety training for field personnel • All shipping and handling of material • Job demobilization and job site clean up • 1-year workmanship warranty 		70,600.00	70,600.00T
Total			



Rack ' M Up Equipment Distributors

Ste D
Wood Dale, IL 60191

Proposal

Proposal Date: 2/7/2024

Proposal #: 1114

Project:

Bill To:

DuPage County Vehicle Maintenance
421 N. County Farm Road
Whaton, Illinois 60187

Description	Est. Hours/Qty.	Rate	Total
<p>Sub Contract Electrical</p> <p>Scope of work:</p> <ul style="list-style-type: none"> • Furnish labor to electrically disconnect existing truck lifts. Make safe for removal by others. • Furnish labor and material to electrically connect 7 new K400-X-M truck lifts. • Use 5 existing 3 pole 60-amp circuit breakers in MDP-1 • Add 1 new 3-pole 60-amp circuit breaker to MDP-1 • Add 1-new 3-pole 60-amp circuit breaker to MDP-2 • Mount new service disconnect switch to side of new counsel - disconnect is rated NEMA3R - (enclosures are engineered for indoor or outdoor use and protect against rain, sleet, snow, dirt, and prevents the formation of ice on its enclosure) • We are assuming that the existing conduit located under ground from service panel to the lift control stations are in good shape and will allow us to repull new wiring. If this is not the case additional cost will be incurred to install new conduit as needed. <p>Furnish the following items:</p> <ul style="list-style-type: none"> • Labor to disconnect existing • Labor and Materials - re-pull new #6 THWN wire to each lift • 250-volt 60-fused disconnect switches for each lift -switches are NEMA 3R • Connection to new counsel • Lot material to install • Lot labor to install 	7	11,422.30	79,956.10T
Total			



Rack ' M Up Equipment Distributors

Ste D
Wood Dale, IL 60191

Proposal

Proposal Date: 2/7/2024

Proposal #: 1114

Project:

Bill To:

DuPage County Vehicle Maintenance
421 N. County Farm Road
Whaton, Illinois 60187

Description	Est. Hours/Qty.	Rate	Total
<p>Sub Contract Electrical - continued -</p> <ul style="list-style-type: none"> • Furnish prevailing wage labor to complete installation. • All work is to be completed during normal working hours 7:00 am through 2:30 pm Monday - Friday. • If above work is subject to city approval by local authority. Additional cost to the owner may be incurred. <p>Warranty</p> <ul style="list-style-type: none"> • Labor warranted for one year from completion of project. Material to be warranted by manufacture <p>Not included</p> <ul style="list-style-type: none"> • Permit/ Permit fees • Additional insurance • Premium labor • Saw cutting. Concrete removal - by concrete sub • New conduit or repair of cut conduit under floor by Rack' M UP • Relocation of conduit under floor • Control or safety wiring 			
<p>Decomm and Removal of Old Lifts Provide labor and equipment to remove existing lifts including disposal of lifts Hydraulic oil to be disposed of in customers waste oil tank.</p>	7	7,139.28571	49,975.00
<p>Allowance to the contract to be used for unforeseen inground items to be used with the fleet supervisors permission. Such unforeseen items to include but no limited to damaged electrical conduit, unmarked drains or vent piping, etc. This is not to be used for known and marked items that are damaged due to negligence or error.</p>	1	35,000.00	35,000.00T
Total			\$769,491.10