

## SPECIFICATIONS

DuPage County ("County") is seeking contractors to provide vehicle upfit services for two (2) vehicles (Ford Transit MID ROOF 148" WB cargo Van) for its Animal Services Department located at 120 North County Farm Road, Wheaton, IL 60187. The objective of this project is to modify existing or newly acquired vehicles to meet operational needs for the transportation and handling of animals in a safe, efficient, and humane manner.

### SPECIFICATIONS

The Contractor shall provide all necessary labor, materials, equipment, and services to modify two (2) vehicles (Ford Transit MID ROOF 148" WB cargo Van) for Animal Services as per the specifications outlined in this document. The upfit process shall include conversion and installation of specialized animal compartments, safety equipment, and other modifications to ensure the vehicles are suitable for the transportation of animals and related operations. The conversation shall include Installation of 9 Sloped & Drained Cages (4 Rear & 5 Inline), Polycarbonate Viewing Window in Upper Passenger Side Rear Cage, Scratch Resistant Polycarbonate Cage Doors, Cage Area Lighting, Polymax Floor Grills, Sealed & Carpeted Cab Divider Wall with Polycarbonate Viewing Window, Sheeted Cargo Area w/Diamond Plate Flooring. For Extended Length Vehicles -Additional Cargo Space Between Cages. No modification or substitution is allowed.

### VEHICLE #1 - FORD TRANSIT MID ROOF 148" WB CARGO VAN

Contractor shall provide:

- **Rear Cage Setback**
  - Cage door with stainless steel rod animal cage door
  - Catch pole cutout to stainless steel rod door (2-interior lower cage – top of door; 2-rear facing lower cage-side of door).
  - Closed storage above bank of side cages
  - Lipped open storage above cage bank.
- **Rear Cage Bank**
  - Roof angle with bungee holes above lipped open storage for cage bank
  - Bungee holes added to lipped storage (48")
  - Storage built into cab divider wall with side access door at passenger side cargo door.
  - Storage closet behind the wheel well on the passenger side with paddle handle and lock (floor to ceiling: 15" W x 11" D; shelf-36"H).
  - Auxiliary Heat/AC installed in gas engine.
  - Installation cab File Desk
  - Thermometer for temperature monitoring
- **Catch Pole Holder**
  - Installed in Rear Driver Side-Side Trimwork
- **Floor Drain in Cargo Area**
  - Install Drain in Rear Set Back Area
- **Catch Pole Hook Install Kit**
  - Install Just Above Window on Cab Wall
- **Amber LED Mini Lightbar, 14.7" L X 9.5" W X 2" H – Installed**
  - Install Top Front of Vehicle

- **Whelen TAL85 traffic advisor with controller**

- Install Top Rear of Van

All work shall comply with federal, state, and local regulations and standards for animal transportation. Modifications must meet the operational needs of Animal Services personnel and be designed for long-term durability.

## **VEHICLE #2 - FORD TRANSIT MID ROOF 148" WB CARGO VAN**

Contractor shall provide:

- **Rear Cage Setback**

- Cage door with stainless steel rod animal cage door
- Catch pole cutout to stainless steel rod door (2-interior lower cage – top of door; 2-rear facing lower cage-side of door).
- Closed storage above bank of side cages
- Lipped open storage above cage bank.

- **Rear Cage Bank**

- Roof angle with bungee holes above lipped open storage for cage bank
- Bungee holes added to lipped storage (48")
- Storage built into cab divider wall with side access door at passenger side cargo door.
- Storage closet behind the wheel well on the passenger side with paddle handle and lock (floor to ceiling: 15" W x 11" D; shelf-36"H).
- Integration of rear AC option in Ford Transit Cargo Van
- Integration of front factory heat in Ford Transit Cargo Van
- Installation cab File Desk
- Thermometer for temperature monitoring

- **Catch Pole Holder**

- Installed in Rear Driver Side-Side Trimwork

- **Floor Drain in Cargo Area**

- Install Drain in Rear Set Back Area

- **Catch Pole Hook Install Kit**

- Install Just Above Window on Cab Wall

- **Amber LED Mini Lightbar, 14.7" L X 9.5" W X 2" H – Installed**

- Install Top Front of Vehicle

- **Whelen TAL85 traffic advisor with controller**

- Install Top Rear of Van

## **Price**

Contractor shall provide pricing in Section 1 for each Vehicle Conversion and Installation. In Section 2, contractor shall provide its shipping method.

## PRICE

Quantities listed are canvassing quantities and intended to establish pricing.

### SECTION 1

NO	ITEM	UOM	QTY	PRICE	EXTENDED PRICE
<b>Vehicle 1 - FORD TRANSIT MID ROOF 148" WB CARGO VAN</b>					
1	Conversion	EA	1	\$ 37,083.60	\$ 37,083.60
Installation of Equipment					
2	Rear Cage Setback	EA	1	\$ 0.00	\$ 0.00
3	Rear Cage Bank	EA	1	\$ included	\$ included
4	Auxiliary Heat/AC install in Gas Engine	EA	1	\$ 3,584.40	\$ 3,584.40
5	Installation of Cab File Desk	EA	1	\$ 493.20	\$ 493.20
6	Installation of Thermometer	EA	1	\$ 204.00	\$ 204.00
7	Catch Pole Holder (install in rear driver side-side trimwork)	EA	1 2 ea	\$ 310.80	\$ 621.60
8	Floor Drain in Cargo Area (install drain in rear set back area)	EA	1	\$ 152.40	\$ 152.40
9	Catch Pole Hook Install Kit (install just above window on cab wall)	EA	1 2 ea	\$ 68.40	\$ 136.80
10	Amber LED Mini Lightbar, 14.7" L X 9.5" W X 2" H (Install top front of vehicle)	EA	1	\$ 786.00	\$ 786.00
11	Whelen TAL85 traffic advisor with controller (install top rear of van)	EA	1	\$ 1,909.20	\$ 1,909.20
12	Shipping	EA	1	\$ N/A	\$ N/A
<b>Vehicle 2 - FORD TRANSIT MID ROOF 148" WB CARGO VAN</b>					
13	Conversion	EA	1	\$ 37,576.80	\$ 37,576.80
Installation of Equipment					
14	Rear Cage Setback	EA	1	\$ 0.00	\$ 0.00
15	Rear Cage Bank	EA	1	\$ included	\$ included
16	Integration of rear factory AC option in van	EA	1	\$ 693.60	\$ 693.60
17	Integration of front factory Heat in van	EA	1	\$ 693.60	\$ 693.60
18	Installation of Thermometer	EA	1	\$ 204.00	\$ 204.00

NO	ITEM	UOM	QTY	PRICE	EXTENDED PRICE
19	Catch Pole Holder (install in rear driver side-side trimwork)	EA	1 2 ea	\$ 310.80	\$ 621.60
20	Floor Drain in Cargo Area (install drain in rear set back area)	EA	1	\$ 152.40	\$ 152.40
21	Catch Pole Hook Install Kit (install just above window on cab wall)	EA	1 2 ea	\$ 68.40	\$ 136.80
22	Amber LED Mini Lightbar, 14.7" L X 9.5" W X 2" H (install top front of vehicle)	EA	1	\$ 786.00	\$ 786.00
23	Whelen TAL85 traffic advisor with controller (install top rear of van)	EA	1	\$ 1,909.20	\$ 1,909.20
24	Shipping	EA	1	\$ N/A	\$ N/A
GRAND TOTAL					\$ 87,745.20
GRAND TOTAL (In words)					

## SECTION 2

Contractor shall provide shipping method.

☒ Customer Pick up / Dropoff.

☐ F.O.B. Destination

☐ F.O.B. Shipping Point

QUOTE SIGNATURE PAGE

VEHICLE UPFIT FOR ANIMAL SERVICES 24-115-ANS

X\_\_\_\_\_



Account Executive

\_\_\_\_\_  
(Signature and Title)

10/11/2024

\_\_\_\_\_  
(Date)

QUOTATION MUST BE SIGNED FOR CONSIDERATION

(PLEASE TYPE OR PRINT THE FOLLOWING INFORMATION)

Full Business Name of Bidder	MAVRON, INC.
Main Business Address	152 S Zimmer Rd.
City, State, Zip Code	Warsaw, IN 46580
Telephone Number	574-267-3044 / 1-800-551-1498
Email Address	terri@mavron.com
Bid Contact Person	Terri Lambright, 574-371-2402