



Worldwide Pipeline  
Rehabilitation

1334 Enterprise Drive  
Romeoville, IL 60446

Cell: 630-842-8539  
Fax: 708-478-4871  
kcoburn@azuria.com

DuPage County Public Works  
Sean Reese – Manager of Public Works Operations  
7900 S. Route 53  
Woodridge, IL 60517  
Via Email: Sean.Reese@dupagecounty.gov

January 13, 2026

**Re: DuPage County – Lift Stations at County Jail – Omnia Contract #23-065 PW**

Insituform Technologies USA, LLC. (Contractor) will provide services to complete the following Insituform® work on the above referenced project:

**Scope of Work:**

Item	Description	QTY	Unit	Unit Price	Total
<b>Lift Station #1</b>					
508	Travel and Mobilization	1	LS	\$ 8,000.00	\$ 8,000.00
382	MH/Structure - (Sand Blasting & Primer Preparation)	1790.0	SQFT	\$ 95.00	\$ 170,050.00
382	MH/Structure - Spray Rehabilitation	1790.0	SQFT	\$ 110.00	\$ 196,900.00
TBD	Bypass Allowance	1	LS	Lump Sum	\$ 40,000.00
110	Bypass Pump Watch Labor Allowance	21	Days	\$ 2,000.00	\$ 42,000.00
111	Bypass Line Watch Labor Allowance	21	Days	\$ 1,500.00	\$ 31,500.00
				<b>Total</b>	<b>\$ 488,450.00</b>
<b>Lift Station #2 (DuPage County Jail)</b>					
508	Travel and Mobilization	1	LS	\$ 7,000.00	\$ 7,000.00
382	MH/Structure - (Sand Blasting & Primer Preparation)	455.0	SQFT	\$ 95.00	\$ 43,225.00
382	MH/Structure - Spray Rehabilitation	455.0	SQFT	\$ 110.00	\$ 50,050.00
TBD	Bypass Allowance	1	LS	Lump Sum	\$ 20,000.00
110	Bypass Pump Watch Labor Allowance	7	Days	\$ 2,000.00	\$ 14,000.00
111	Bypass Line Watch Labor Allowance	7	Days	\$ 1,500.00	\$ 10,500.00
				<b>Total</b>	<b>\$ 144,775.00</b>
<b>Grand Total</b>					<b>\$ 633,225.00</b>

**Note: This proposal assumes the work at both lift stations will be performed together and the prices are tied together.**

**Note: The 2,245 SQFT quantity includes 257 SQFT of smaller pipes that need to be sprayed as discussed during the site visit.**

**Note: The bypass details were not available at the time of this proposal and will be finalized once full details are worked out. Therefore, a bypass allowance is provided.**

- Included:
  - Sandblasting, Primer (N69F) and epoxy coating (Epoxytec 456)
  
- By others:
  - All lift station and valve box components are to be removed prior to our arrival.
  - All pipe demo, pump removal, electrical, and installation of new piping and equipment.
  - The system must be dewatered prior to arrival.
  - Provide an adequate water supply (i.e., fire hydrant, water truck, etc.) for the Combo Unit (ITI equipment carries 2.5” NH Couplings. If the hookup requires something other than this, please notify prior to arrival).
  
- All materials are to be applied per the manufacturer’s specifications.

**Note: All work will be completed in accordance with the specifications and bid documents entitled County of DuPage/Omnia Contract #23-065 PW TRENCHLESS REHABILITATION AND MAINTENANCE OF PIPELINE INFRASTRUCTURE 23-065-PW bid on 11/28/23.**

Sincerely,  
**INSITUFORM TECHNOLOGIES USA, LLC.**



Kevin Coburn, Vice President of Sales, Midwest & NE, Cell – 630-842-8539  
\*\*\*\*\*

DuPage County

Signed: \_\_\_\_\_

Printed Name/Title: \_\_\_\_\_ Date: \_\_\_\_\_

**This accepted proposal constitutes a formal agreement. If you initiate a purchase order or other contract document it shall not be acknowledged without this accepted proposal as an attachment.**

Accepted By: Insituform Technologies USA, LLC.

**By:** \_\_\_\_\_

**Date:** \_\_\_\_\_