DUPAGE 21 1 PROJECT NO. 211350

DUPAGE COUNTY CAMPUS STORMWATER POND IMPROVEMENTS FINAL ENGINEERING PLANS

INDEX OF SHEETS

TITLE SHEET GENERAL NOTES


0

0

0

- EXISTING CONDITIONS EAST FAIRGROUNDS POND
- REMOVAL PLAN EAST FAIRGROUNDS POND
- 5-6 GRADING PLAN EAST FAIRGROUNDS POND
- UTILITY PLAN EAST FAIRGROUNDS POND PAVING PLAN - EAST FAIRGROUNDS POND
- EROSION CONTROL PLAN EAST FAIRGROUNDS POND
- PLANTING PLAN EAST FAIRGROUNDS POND
- 12 REFERENCE: BATHYMETRIC SURVEY BY OTHERS EAST FAIRGROUNDS POND
- REFERENCE: 2001 PLAN (BY OTHERS) REFERENCE EAST FAIRGROUNDS POND SWPPP AND EROSION CONTROL NOTES
- 15-16 EROSION CONTROL DETAILS
- 17-21 CONSTRUCTION DETAILS

CITY OF WHEATON **DUPAGE COUNTY, ILLINOIS**



LEGEND PR STORM SEWER PR STORM SEWER (BY OTHERS) PR MAJOR CONTOURS PR MINOR CONTOURS PR TRENCH BOX PR DRAINAGE STRUCTURE (CLOSED LID / OPEN LID) PR DRAINAGE STRUCTURE, BY OTHERS (CLOSED LID / OPEN LID) PR FLARED END SECTION PR SIGN PANEL EX STORM SEWER FX MAIOR CONTOURS EX MINOR CONTOURS ------ EX SANITARY SEWER EX WATER SERVICE LINE EX UNDERGROUND ELECTRIC

EX UNDERGROUND TELEPHONE EX OVERHEAD ELECTRIC

EX PROPERTY BOUNDARY --- EX EDGE OF WATER

----- EX FENCE LINE

EX UNDERGROUND GAS

EX DRAINAGE STRUCTURE

EX FLARED END SECTION EX DECIDUOUS TREE

EX EVERGREEN TREE

STMP EX STUMP

EX WATER VALVE EX LIGHT POLE

EX HANDHOLE

□ T EX COMMUNICATION BOX

EX COMMUNICATION STRUCTURE

EX POWER POLE

DRAWING DATE: 04-10-2023

REVISIONS:

- 1. 4-14-2023 (PER DUPAGE COUNTY COMMENTS)
- 2. 4-18-2023 (PER DUPAGE COUNTY COMMENTS AND RECEIPT OF SURVEY)
- 3. 5-2-2023 (REMOVE SPOIL PILE)

OWNER:

DUPAGE COUNTY FACILITIES 421 COUNTY FARM RD WHEATON, IL 60187

CONTACT:

GEOFFREY MATTESON DUPAGE COUNTY FACILITIES MANAGEMENT 630-407-5681

BENCHMARKS

SOURCE: 2006 GEODETIC SURVEY MONUMENT

STATION DESIGNATION: BENCHMARK 0001 ESTABLISHED BY: DUPAGE COUNTY DATE: IANUARY 2006

ELEVATION: 727.89 DATUM: NAVD 88

SOURCE: 2006 GEODETIC SURVEY MONUMENT

STATION DESIGNATION: BENCHMARK 0002 ESTABLISHED BY: DUPAGE COUNTY DATE: JANUARY 2006 PID: DK3250

ELEVATION: 726.06

FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES.

PROFESSIONAL ENGINEER'S SIGN AND SEAL

JENNIEER N H MAERCKIEIN P.E. #062-055729 EXP. DATE;

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION 1-800-892-0123 OR 811



TELEPHONE MR, STEVEN PESOLA 1000 COMMERCE DRIVE OAK BROOK, IL 60523 (630) 573-5703

WATER AND SEWER
ILLINOIS AMERICAN WATER MR. CHARLES SCHAEFER (618) 239-3273

NICOR MR. CHARLES M. PARROTT 1844 FERRY ROAD NAPERVILLE, IL 60563 (630) 388-3319

GENERAL NOTES

- ALL EXISTING TOPOGRAPHY, UNDERGROUND UTILITIES, STRUCTURES AND ASSOCIATED FACILITIES SHOWN ON THESE DRAWINGS HAVE BEEN PLOTTED FROM AVAILABLE SURVEYS AND RECORDS. THEREFORE, THEIR LOCATIONS AND ELEVATIONS MUST BE CONSIDERED APPROXIMATE ONLY THERE MAY BE OTHER FACILITIES. THE EXISTENCE OF WHICH ARE NOT PRESENTLY KNOWN. THE EXACT LOCATIONS AND ELEVATIONS ARE TO BE VERIFIED BY THE CONTRACTOR.
- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" FOR FIELD LOCATIONS OF BURIED UTILITIES 48 HOURS IN ADVANCE OF WORK
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO FIELD CHECK ALL DIMENSIONS AND ELEVATIONS OF EXISTING UTILITY LINES AND STRUCTURES THAT MAY BE IMPACTED BY THE PROPOSED WORK PRIOR TO ORDERING MATERIAL OR BEGINNING CONSTRUCTION. ANY DISCREPANCIES FROM THE PLANS SHALL BE REPORTED TO THE ENGINEER IMMEDIATELY.
- 4. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED BY THE UTILITY COMPANY AT THE CONTRACTOR'S EXPENSE
- THE CONTRACTOR SHALL USE ALL NECESSARY PRECAUTIONARY AND PROTECTIVE MEASURES REQUIRED TO MAINTAIN AND PROTECT EXISTING LITHTIES. SEWERS, MAINS AND APPURTENANCES THAT MUST BE KEPT IN OPERATION. IN PARTICULAR, THE CONTRACTOR SHALL TAKE ADEQUATE MEASURES TO PREVENT THE UNDERMINING OF UTILITIES, SEWERS AND MAINS WHICH WILL REMAIN IN SERVICE. THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER AND UTILITY COMPANY IF IT IS DETERMINED THAT TEMPORARY BRACING OR SUPPORT OF THE UTILITIES IS REQUIRED. THE PROTECTION AND/OR TEMPORARY BRACING OR SUPPORT OF UTILITIES WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICES OF THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- THE CONTRACTOR WILL NOT BE PERMITTED TO SET UP A YARD OR FIELD OFFICE ON COUNTY, CITY, TOWNSHIP, OR PRIVATE PROPERTY WITHOUT PRIOR WRITTEN PERMISSION
- WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED. THE ENGINEER SHALL RE NOTIFIED BEFORE SUCH MONUMENTS ARE DISTURBED. THE CONTRACTOR SHALL CAREFULLY
 PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER, AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED EACH LOCATION.
- ALL APPLICABLE PROVISIONS OF THE CURRENT OCCUPATIONAL SAFETY AND HEALTH ACT ARE HEREIN INCORPORATED BY REFERENCE.
- EXCEPT WHERE MODIFIED BY THE CONTRACT DOCUMENTS, ALL WORK PROPOSED HEREON SHALL BE IN ACCORDANCE WITH THE FOLLOWING SPECIFICATIONS WHICH ARE HEREBY
 - "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION IN ILLINOIS," AS PREPARED
 - "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS." AS PREPARED BY IDOT, LATEST EDITION.
 - c. THE ILLINOIS ACCESSIBILITY CODE.
 - "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES d. FOR STREETS AND HIGHWAYS," LATEST EDITION
 - "STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS AS PUBLISHED BY THE IEPA." LATEST EDITION.
 - ILLINOIS RECOMMENDED STANDARDS FOR SEWAGE WORKS," AS PUBLISHED BY THE IEPA LATEST EDITION.
 - "MANUAL OF TEST PROCEDURES FOR MATERIALS."
 - h. "ILLINOIS URBAN MANUAL," LATEST EDITION
 - THE NATIONAL ELECTRIC CODE, LATEST EDITION,
- 10. THE ENGINEER AND DUPAGE COUNTY ARE NOT RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES OR PROCEDURES, TIME OF PERFORMANCE PROGRAMS OR ANY SAFETY PRECAUTIONS USED BY THE CONTRACTOR, THE CONTRACTOR IS SOLELY RESPONSIBLE FOR EXECUTION OF HIS/HER WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS AND SPECIFICATIONS.

- 11. THE CONTRACTOR IS RESPONSIBLE FOR HAVING A SET OF "APPROVED" ENGINEERING PLANS WITH THE LATEST REVISION DATE ON THE JOB SITE PRIOR TO THE START OF CONSTRUCTION AND AT ALL TIMES DURING CONSTRUCTION.
- 12 AREAS OUTSIDE THE RIO WILLING OR CONSTRUCTION LIMIT LINE IMPACTED BY OPERATIONS OF THE CONTRACTOR SHALL BE RETURNED TO THE STATE IT WAS FOUND PRIOR TO NEW CONSTRUCTION. EXCEPT WHERE NEW WORK IS SHOWN.
- 13. CONTRACTOR SHALL MAINTAIN ACCESS TO ALL PROPERTIES AND SIDE ROADS
- CONSTRUCTION ACTIVITY IS ALLOWED SEVEN DAYS A WEEK, FROM 7:00 AM TO SUNSET, NOISE FROM CONSTRUCTION AND DEMOLITION ACTIVITY IS UNRESTRICTED, FROM SUNSET TO 7:00 AM, NOISE IS LIMITED TO 50 DECIBELS, SIMILAR TO A NORMAL CONVERSATION.

REMOVALS, GRADING, AND PAVING NOTES

- ALL EXISTING PAVEMENT TO BE REMOVED SHALL BE SAWCUT ALONG LIMITS OF PROPOSED REMOVAL BEFORE COMMENCEMENT OF PAVEMENT REMOVAL. THE COST OF THE SAW CUT SHALL BE INCLUDED IN THE COST OF ITEM
- 2. NO HOLES ARE TO BE LEFT OPEN IN THE PAVEMENT OR PARKWAY OVER A HOLIDAY. WEEKEND OR AFTER 3:00 P.M. ON THE DAY PRECEDING A HOLIDAY OR A WEEKEND.
- STREET PAVING AND CURBS TO REMAIN SHALL BE PROTECTED FROM DAMAGE, IF DAMAGED, IT SHALL BE REPLACED PROMPTLY IN CONFORMANCE WITH THE MUNICIPALITY OR IDOT STANDARD SPECIFICATIONS IN MATERIALS AND WORKMANSHIP AND AT THE CONTRACTOR'S EXPENSE.
- 4 ASPHALT JOINTS FOR BINDER COURSES ARE TO BE STAGGERED.
- 5. PROPOSED ELEVATIONS INDICATE FINISHED CONDITIONS. FOR ROUGH GRADING ELEVATIONS ALLOW FOR THICKNESS OF PROPOSED PAVING (ROADS, WALKS, DRIVES, ETC.) OR TOPSOIL AS INDICATED ON DRAWINGS.
- 6. EARTH EXCAVATION MATERIAL MOVED MORE THAN ONCE, AND STOCKPILED FOR USE AT A ATER TIME, SHALL NOT BE PAID FOR A SECOND TIME, UNLESS APPROVED BY THE ENGINEER.
- 7 EXCAVATED TOPSOIL MAY BE STRIPPED TO A STOCKPILE AND PAID FOR A SECOND TIME TO RESPREAD THE TOPSOIL FROM THE STOCKPILE TO FINISHED GRADE, IT SHALL NOT BE PAID FOR A THIRD TIME, UNLESS APPROVED BY THE ENGINEER.

DRAINAGE NOTES

- ALL FIELD TILE ENCOUNTERED DURING CONSTRUCTION OPERATIONS SHALL BE CONNECTED TO THE PROPOSED STORM SEWER OR EXTENDED TO OUTLET INTO A PROPOSED DRAINAGE TO THE PROPUSED STORM SEWER OR EXTENDED TO OUTLET TIME A PROPOSED DRAINAGE WAY AS DETERMINED BY THE REGINIERE, IF IT THIS CANNOT BE ACCOMPLISHED, THEN IT SHALL BE REPAIRED WITH NEW PIPE OF SIMILAR SIZE AND MATERIAL TO THE ORIGINAL LINE AND PUT IN ACCEPTABLE OPERATIONAL CONDITION. A RECORD OF THE LOCATION OF ALL FIELD TILE FOR ON-SITE ORAIN PIPE ENCOUNTERED SHALL BE KEPT BY THE CONTRACTOR AND SUBMITTED TO THE ENGINEER UPON COMPLETION OF THE PROJECT.
 ALL FIELD TILE REPAIRS MUST MEET THE ILLINOIS URBAN MANUAL SPEC 945. THE COS' OF THIS WORK SHALL BE CONSIDERED AS INCIDENTAL TO THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE PROVIDED.
- WHEN AN EXISTING DRAINAGE ROUTE, EITHER A STORM SEWER OR WATERWAY, IS INTERRUPTED DUE TO THE SEWER INSTALLATION, THE DRAINAGE ROUTE SHALL BE RE-ESTABLISHED TO ORIGINAL CONDITIONS BY THE END OF THE SAME WORK DAY, POSITIVE DRAINAGE MUST BE MAINTAINED AT ALL TIMES DURING CONSTRUCTION.
- DURING CONSTRUCTION THE CONTRACTOR SHALL MAINTAIN ALL SURFACE DRAINAGE WITHIN PROJECT LIMITS. ALL STORM FLOW MUST BE MAINTAINED AT ALL TIMES, UNLESS OTHERWISE DIRECTED BY ENGINEER.
- WHENEVER, DURING CONSTRUCTION OPERATIONS, LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF GUTTERS, DRAINAGE STRUCTURES, DITCHES ETC., SUCH THAT THE NATURAL FLOW LINE OF WATER IS OBSTRUCTED, THE LOOSE MATERIAL SHALL BE REMOVED AT THE CLOSE OF EACH WORKING DAY, AT THE CONCLUSION OF THE CONSTRUCTION OPERATION, ALL DRAINAGE STRUCTURES AND FLOW LINES SHALL BE FREE FROM DIRT AND DEBRIS. THIS WORK SHALL BE INCLUDED IN THE COST OF THE CONTRACT. THE CONTRACTOR'S FAILURE TO PROVIDE THE ABOVE WILL PRECLUDE ANY POSSIBLE ADDED COMPENSATION REQUESTED DUE TO DELAYS OR UNSUITABLE MATERIAL CREATED AS A RESULT THEREOF
- ANY EXISTING DRAINAGE FACILITIES DISTURBED OR DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AT THEIR EXPENSE. THIS WORK SHALL BE PERFORMED TO THE SATISFACTION OF THE ENGINEER.
- OFFSETS AND TOP OF FRAME OR LID ELEVATIONS FOR STRUCTURES LOCATED IN THE GUTTER ARE GIVEN AT THE EDGE OF PAVEMENT.
- TOP OF FRAME ("RIM") FLEVATIONS GIVEN ON THE PLANS ARE ONLY TO ASSIST THE CONTRACTOR IN DETERMINING THE APPROXIMATE OVERALL HEIGHT OF EACH STRUCTURE. FRAMES ON ALL NEW STRUCTURES SHALL BE ADJUSTED TO THE FINAL ELEVATIONS OF THE AREAS IN WHICH THEY ARE LOCATED, AS PART OF THE STRUCTURE COST.
- EXISTING MANHOLE / CATCH BASIN RIMS SHALL BE ADJUSTED AS NOTED.
- UNLESS OTHERWISE INDICATED ON THE PLANS, STORM SEWER PIPE SHALL BE REINFORCED CONCRETE PIPE IN CONFORMANCE WITH IDOT STANDARD SPECIFICATIONS DETERMINATION FOR PIPE CLASS, AND CONFORMING TO ASTM C76. ALL STORM SEWER SHALL HAVE GASKETED JOINTS CONFORMING TO ASTM C-361.

- STORM SEWER CASTING THAT ARE NOT TO BE RE-USED SHALL BE RETURNED TO DUPAGE COUNTY.
- THE COST OF MAKING STORM SEWER CONNECTIONS TO EXISTING OR PROPOSED SEWER OR DRAINAGE STRUCTURES SHALL BE INCLUDED IN THE COST OF THE STORM SEWER BEING
- 12. PROVIDE TRENCH BACKFILL IN ACCORDANCE WITH IDOT SPECIFICATIONS.
- 13. THE CONTRACTOR SHALL FURNISH ALL LABOR, EQUIPMENT AND MATERIAL NECESSARY FOR DEWATERING EXCAVATIONS AS WELL AS SHORING TRENCH WALLS DURING GRADING, UTILITY AND STORM SEWER OPERATIONS. THE COST OF COMPLIANCE WITH THE ABOVE, SHALL BE INCLUDED IN THE COST OF THE UTILITY BEING INSTALLED.

MAINTENANCE OF TRAFFIC NOTES

- 1. TRAFFIC CONTROL AND PROTECTION SHALL BE PERFORMED IN ACCORDANCE WITH THE MAINTENANCE OF TRAFFIC NOTES AND PROTECTION SECTION 701 OF THE STANDARD
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ADEQUATE SIGNS, TRAFFIC CONTROL DEVICES AND WARNING DEVICES TO INFORM AND PROTECT THE PUBLIC DURING ALL PHASES OF CONSTRUCTION, BARRICADES AND WARNING SIGNS SHALL BE PROVIDED IN ACCORDANCE WITH ARTICLE 107.14 OF THE IDOT STANDARD SPECIFICATIONS, ALL TRAFFIC CONTROL WORK SHALL BE DONE IN ACCORDANCE WITH IDOT "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES."
- 3. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL PROPERTIES AT ALL TIMES DURING CONSTRUCTION OPERATIONS LINESS OTHERWISE NOTED ON PLANS
- 4. ALL TRAFFIC CONTROL DEVICES SHALL BE MAINTAINED THROUGH THE COMPLETION OF
- 5. ALL HOLES MUST BE PLATED OR FILLED BEFORE COMPLETION OF THE WORK DAY.
- 6. ALL TRAFFIC CONTROL DEVICES ARE CONSIDERED INCIDENTAL TO THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE PROVIDED.

IDOT HIGHWAY STANDARDS

PRECAST REINFORCED CONCRETE FLARED END SECTION 542301-03 CATCH BASIN, TYPE A MANHOLE STEPS 602001-02 602701-02 604036-03 FRAME AND GRATE TYPE 8 TRAFFIC CONTROL DEVICES 701901-08 720006-04 SIGN PANEL ERECTION DETAILS METAL POSTS FOR SIGNS, MARKERS & DELINEATORS 729001-01 APPLICATIONS OF TYPES A & B METAL POSTS

ILLINOIS URBAN MANUAL STANDARDS

EROSION CONTROL BLANKET INSTALLATION DETAILS IUM-530 IUM-617A FLOATING SILT CURTAIN - TYPICAL LAYOUT FLOATING SILT CURTAIN - PANEL CONNECTORS STABILIZED CONSTRUCTION ENTRANCE PLAN IUM-617B IL-630 11-650 SLIMP PIT PLAN ROCK OUTLET PROTECTION 11-910

3.724.9200 pho 3.724.9202 fax


EVISED REVISED CHECKED -JNHM REVISED DATE REVISED


DUPAGE COUNTY CAMPUS STORMWATER POND IMPROVEMENTS MINFIELD / WHEATON ENGINEERING PLANS


GENERAL NOTES


COUNTY DUPAGE 21 CONTRACT NO. 19172 03

ILLINOIS SCALE: 1"=40" SHEET 1 OF 1 SHEETS STA.









PROPOSED EAST FAIRGROUND POND

ELEVATION	AREA (acres)	AVERAGE AREA (acres)	STAGE VOLUME (acre-feet)	CUMULATIVE VOLUME (acre-feet)	COMMENT
717.00	5.41				
717.73	5.55			0.00	NWL
740.00	F 50	5.575	1.505	4.64	
718.00	5.60	5.705	5.705	1.51	
719.0	5.81	3.703	5.705	7.21	
	2000	5.895	5.895		
720.0	5.98			13.11	
Î		6.065	6.065		
721.0	6.15			19.17	
		6.250	6.250		
722.0	6.35	6.475	6.475	25.42	
723.0	6.60	6.475	6.475	31.90	
723.0	0.00	6.745	6.745	31.90	
724.0	6.89	VT.000.0007	3237330	38.64	
		7.010	7.010		
725.0	7.13			45.65	
725.15		7.230	7.230	46.73	overtopping / HWL
726.0	7.33			52.88	
		7.435	7.435		
727.0	7.54			60.32	


COUNTY TOTAL SHEETS NO.


DUPAGE 21 6


PROJECT NO. 211350


(\mathbf{V})	V3 Companies 7325 Janes Aven Woodridge, IL 60 630,724,9200 ph 630,724,9202 fa: www.v3co.com

USER NAME = cray	DESIGNED - CEB	REVISED -	REVISED -	DUPAGE COUNTY CAMPUS		PROPOSED GRADING PLAN -
	DRAWN - CMR	REVISED -	REVISED -	STORMWATER POND IMPROVEMENTS		
PLOT SCALE =	CHECKED - JNHM	REVISED -	REVISED -	ENGINEERING PLANS		FAIRGROUNDS POND
PLOT DATE = 5/1/2023	DATE -	REVISED -	REVISED -	WINFIELD / WHEATON ENGINEERING PLANS ILLINOIS	Z-SCALE: 20:1	SHEET 2 OF 2 SHEETS STA.









	(4,500 plugs per acre)	
Species	Common Name	Quantity
Acorus calamus	Sweet Flag	1,500
Iris virginica shrevei	Blue Flag	1,500
Juncus effusus	Soft Rush	1,500
Pontederia cordata	Pickerelweed	2000
Sagittaria latifolia	Common Arrowhead	1,500
Schoenoplectus fluviatilis	River Bulrush	2,700
Scirpus acutus	Hardstern bulrush	ر, 700°°° ا
Scirpus pungens	Chairmaker's Rush	2,100
Scirpus validus creber	Great Bulrush	2,700
Sparganium eurycarpum	Bur Reed	2,700
	Total:	20,900

PICKEREL WEED ZONE (1,065 LF)						
Species Common Name Quantity						
Pontederia cordata	Pickerelweed	200				
	200					

WHITE WATER LILY ZONE (0.83 acres)							
Species	Species Common Name Quantity						
Nymphaea tuberosa	White Water Lily	1,500					
	Total:	1,500					

horein		~2' on center in two rows para reline (1,993LF)	arer with the
	Species	Common Name	Quantity
Pla	Carex lacustris	Lake Sedge	250
Ro	Hibiscus laevis	Halberd Leaved Rose Mallow	200
Shoreling Row	Iris virginica shrevei	Blue Flag	200
	Physostegia virginiana	Obedient Plant	150
Pla	Scirpus validus creber	Great Bulrush	200
Ro		Sub Total Plugs:	1,000
	Asclepias incarnata	Swamp Milkweed	200
CI II	Carex emoryi	Riverbank Sedge	200
er Shoreline	Carex pellita	Woolly Sedge	200
Row	Liatris pycnostachya	Prairie Blazing Star	150
	Spartina pectinata	Prairie Cord Grass	250
		Sub Total Plugs:	1,000
		Total Plugs:	2,000

PERFORMANCE STANDARDS FOR PLANTING AT FAIRGROUNDS POND

The following performance standards apply to the planting area at the Fairgrounds Pond. As performance standards are achieved, it is expected that the standard will be maintained until all performance standards are met. Performance standards apply to each vegetation zone separately. If the performance standards are not achieved, the permittee is responsible for correction of any deficiencies through further management activities, which may include replanting.

- 1. Within 3 months of seed installation, at least 80% of the seeded areas (mesic prairie), as measured by aerial coverage, shall be vegetated. A minimum 90% vegetative coverage shall be achieved in the second year and maintained throughout, and at the end of, the three-year period for this area.
- At the end of the second growing season no areas (mesic prairie slopes) shall contain unvegetated areas greater than one square meter. This standard shall be maintained until sign off is achieved.
- 3. At the end of the second growing season, relative coverage of non-native species in the stormwater area cannot exceed 75%. As such, relative coverage of natives shall be 25% or greater at the end of the second growing season. At the end of the third growing season, relative coverage of non-native species in the stormwater areas cannot exceed 25%. As such, relative coverage of natives shall be 75% or greater at the end of the third growing season.
- 4. By the end of each growing season, the top three most dominant species based on relative coverage in each vegetation zone shall not be non-native. Examples of non-native species shall include, but not be limited to, the following: reed canary grass (Phalaris arundinacea); common reed (Phragmites australis); field thistle (Cirsium arvense); buckthorn (Rhamnus spp.); cattails (Typha spp.); teasel (Dipsacus spp.); purple loosestrife (Lythrum salicaria); clover (Trifolium spp.); and sweet clover (Melilotus spp.).
- At the end of the third growing season, 50% vegetative coverage or greater shall be achieved within the stormwater emergent planting zones.
- The stormwater areas shall not contain any rills greater than 3 inches wide and 3 inches deep throughout, and at the end, of the three-year period,
- 7. A Floristic Quality Index (FQI) of 20 and a Coefficient of Conservatism value of 3.5 or greater shall be achieved by the end of the third growing season.


$\overline{\mathbf{V}}$	V3 Companies 7325 Janes Avenue Woodridge, IL 6051 630,724,9200 phon 630,724,9202 fax www.v3co.com


noue	USER NAM
60517	
hone	PLOT SCAL
	PLOT DATE

R NAME = cray	DESIGNED - DJJ	REVISED - 4-14-2023	REVISED -	
	DRAWN - CMR	REVISED - 4-18-2023	REVISED -	1
F SCALE =	CHECKED - JNHM	REVISED	REVISED -	l
F DATE = 5/1/2023	DATE -	REVISED -	REVISED -	WIN

PLANTING PLAN - FAIRGROUNDS POND								COOIL	SHEETS	NO.	1
PERFORMANCE STANDARDS							DUPAGE	21	11		
	FERT ORIVIANCE STANDARDS								PROJECT NO. 211350		
40'	10' SHEET 2 OF 2 SHEETS STA. TO STA.						PROJECT P	10. 211:	330	l	
											•

TOTAL SHEET





<u>Ş</u>	V3 Companies 7325 Janes Avenue Woodridge, IL 60517 630.724.9200 phone 630.724.9202 fax www.v3co.com

USER NAME = cray	DESIGNED -	REVISED	REVISED -
	DRAWN -	REVISED -	REVISED -
PLOT SCALE -	CHECKED -	REVISED -	REVISED -
PLOT DATE = 5/1/2023	DATE	REVISED -	REVISED -

DUPAGE COUNTY CAMPUS
STORMWATER POND IMPROVEMENTS
MRIELD / WHEATON ENGINEERING PLANS
ILLINOIS

REFERENCE: EAST FAIRGROUNDS POND							
2001 DESIGN PLAN BY OTHERS							
SCALE: N.T.S.	SHEET	1	OF	1	SHEETS	STA.	TO STA.

DUPAGE	21	13
PROJECT N	10. 211	350

STORM WATER POLLUTION PREVENTION PLAN NOTES

THIS PLAN HAS REEN PREPARED TO COMPLY WITH THE NPDES PERMIT NUMBER ILR10. ISSUED BY THE LILINOIS ENVIRONMENTAL PROTECTION AGENCY (IEPA) FOR STORMWATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES.

THE PERMITTEE MUST COMPLY WITH ALL CONDITIONS OF THE GENERAL PERMIT. ANY NON-COMPLIANCE CONSTITUTES A VIOLATION OF THE IEPA ACT AND THE CLEAN WATER ACT AND CAN BE GROUNDS FOR ENFORCEMENT ACTION, PERMIT REVOCATION, MODIFICATION, RE-ISSUANCE, TERMINATION, OR DENIAL OF A

1. SITE DESCRIPTION

THE PROJECT WILL INCLUDE STORM SEWER INSTALLATION, PAVEMENT RESTORATION, REGRADING, AND OTHER MINOR IMPROVEMENTS ASSOCIATED WITH THE PROPOSED WORK. THE PROPOSED WORK WILL BE COMPLETED ON THE DUPAGE COUNTY GOVERNMENT CAMPUS ALONG MANCHESTER ROAD IN WHEATON, IL.

CONSTRUCTION SEQUENCE.

A.INSTALLATION OF ALL THE FOLLOWING EROSION CONTROL MEASURES:

- 1. PIPE AND INLET PROTECTION
- 2, STABILIZATED CONSTRUCTION ENTRANCE
- 3. PERIMETER EROSION BARRIER
- 4. GRADING TO EXCAVATE PONDS
- B. INSTALLATION OF PROPOSED STORM SEWER
- C. PROPOSED PAVEMENT IMPROVEMENTS
- D. REMOVAL OF REMAINING EROSION CONTROL ITEMS

CONTROLS.

TEMPORARY STORM WATER POLLUTION PREVENTION MEASURES INTEGRATED INTO THE SITE PLAN INCLUDE THE INSTALLATION OF PIPE PROTECTION AND TEMPORARY STABILIZATION,

EROSION AND SEDIMENT CONTROLS WERE DESIGNED TO:

- A. CONTROL STORM WATER VOLUME AND VELOCITY WITHIN THE SITE TO MINIMIZE SOIL EROSION-
- B. CONTROL STORM WATER DISCHARGES, INCLUDING BOTH PEAK FLOW RATES AND TOTAL STORM WATER COLUME, TO MINIMIZE EROSION AT OUTLETS AND TO MINIMIZE DOWNSTREAM CHANNEL AND STREAM BANK EROSION;
- C. MINIMIZE THE AMOUNT OF SOIL EXPOSED DURING CONSTRUCTION ACTIVITY:
- D. MINIMIZE THE DISTURBANCE OF STEEP SLOPES:

E. MINIMIZE SEDIMENT DISCHARGES FROM THE SITE. THE DESIGN, INSTALLATION AND MAINTENANCE OF EROSION AND SEDIMENT CONTROLS MUST ADDRESS FACTORS SUCH AS THE AMOUNT. EREQUENCY INTENSITY AND DURATION OF PRECIPITATION. THE NATURE OF RESULTING STORM WATER RUNOFF, AND SOIL CHARACTERISTICS, INCLUDING THE RANGE OF SOIL PARTICLE SIZES EXPECTED TO BE

F. PROVIDE AND MAINTAIN NATURAL BUFFERS AROUND SURFACE WATERS, DIRECT STORM WATER TO VEGETATED AREAS TO INCREASE SEDIMENT REMOVAL AND MAXIMIZE STORM WATER INFILTRATION, UNLESS

G. MINIMIZE SOIL COMPACTION AND, UNLESS INFEASIBLE, PRESERVE TOPSOIL,

THE LOCATIONS AND SPECIFICATIONS OF ALL TEMPORARY MEASURES ARE SHOWN ON THE STORM WATER POLLUTION PREVENTION PLAN SHEETS LOCATED AT THE END OF THIS SECTION. THESE MEASURES WILL BE INSTALLED IN ACCORDANCE WITH THE CONSTRUCTION SEQUENCE PREVIOUSLY OUTLINED.

STABILIZATION AND STRUCTURAL PRACTICES

SEVERAL STABILIZATION AND STRUCTURAL PRACTICES HAVE BEEN SELECTED FOR THIS PROJECT TO MINIMIZE EROSION AND THE TRANSPORT OF SEDIMENT FROM THE PROJECT SITE TO OFFSITE AREAS AND RECEIVING WATERS. THESE CONTROLS SHALL BE ACTIVELY MAINTAINED UNTIL FINAL STABILIZATION OF THOSE PORTIONS OF THE SITE UPWARD OF THE PRIMETER CONTROL. THESE PRACTICES INCLUDE:

WORK SHALL BE CONDUCTED IN A MANNER THAT WILL NOT RESULT IN THE GENERATION OF EXCESSIVE AIR BORNE PARTICULATE MATTER OR NUISANCE DUST CONDITIONS.

DUST CONTROL MEASURES MUST BE IMPLEMENTED AT ALL TIMES DURING THE DURATION OF THE PROJECT, INCLUDING NON-WORKING HOURS, WEEKENDS, AND HOLIDAYS AND ARE REQUIRED UNTIL GROUND COVER HAS BEEN ESTABLISHED. COMMON DUST CONTROL MEASURES INCLUDE IRRIGATION OF THE SOIL ON DRY WINDY DAYS. THE USE OF MULCH, VEGETATIVE COVERS, SPRAY ON ADHESIVES, BARRIERS, OR STONE

UPON CONSTRUCTION OF THE STORM SEWER SYSTEM, PIPE PROTECTION AND INLET BASKET FILTERS SHALL BE INSTALLED, PIPE PROTECTION AND INLET BASKET FILTERS IN STORM SEWER STRUCTURES TO BE REMOVED SHALL BE MAINTAINED UNTIL THEIR REMOVAL

ALL DISTURBED AREAS OF THE SITE SHALL BE BROUGHT TO FINAL GRADE, RESPREAD WITH TOPSOIL AND ESTABLISHED WITH PERMANENT VEGETATION AS SOON AS PRACTICABLE.

STABILIZATION ACTIVITIES SHALL BEGIN WITHIN 1 BUSINESS DAY FOR ANY LIN-VEGETATED AREAS THAT ARE SCHEDULED (OR ARE LIKELY) TO BE LEFT INACTIVE FOR FOURTEEN (14) DAYS OR MORE. THE AREAS SHALL BE STABILIZED WITH MEASURES POPURITIES TO THE SEASON TO MINIMIZE EROSION POTENTIAL. STABILIZATION SHALL BE COMPLETED WITH 14 OF THE SEASON TO MINIMIZE EROSION POTENTIAL.

DISTURBED AREAS OF THE SITE SHALL BE GRADED TO DRAIN TO THE STORM SEWER SYSTEM OR POND.

IF SEDIMENT IS ACCIDENTALLY TRANSPORTED ONTO THE STREET IT WILL BE REMOVED FROM THE STREET SURFACE ON A DAILY BASIS.

EXCEPT WHERE MODIFIED ON THIS PLAN, ALL WORK PROPOSED HEREON SHALL BE IN ACCORDANCE WITH DUPAGE COUNTY FLOOD PLAIN AND STORMWATER ORDINANCE AND THE REQUIREMENTS CONTAINED IN ILLINOIS ENVIRONMENTAL PROTECTION AGENCY'S ILLINOIS URBAN MANUAL, LATEST EDITION. IN THE EVENT OF CONFLICTING SPECIFICATIONS WITH REGARD TO SITEWORK ISSUES DESIGNED BY THE ENGINEER, THE MORE

4. STANDARD NOTES:

- A LINIESS OTHERWISE INDICATED ALL VEGETATIVE AND STRUCTURAL PROSION AND SEDIMENT CONTROL PRACTIVES WILL BE CONSTRUCTED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS IN THE MOST RECENT EDITION OF THE ILLINOIS URBAN MANUAL.

C. PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING BUT NOT LIMITED TO, ADDITIONAL PHASES OF DEVELOPMENT AND OFF-SITE BORROW OR WASTE AREAS) A SUPPLEMENTARY EROSION CONTROL PLAN SHALL BE SUBMITTED TO THE OWNER FOR REVIEW

D. DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO SEDIMENT BASINS OR SILT TRAPS.
DEWATERING DIRECTLY INTO FIELD TILES OR STORMWATER STRUCTURES OR WEST ANNEX POND IS PROHIBITED.

F. IT IS THE RESPONSIBILITY OF THE LAND OWNER AND/OR CONTRACTOR TO INFORM ANY SUB-CONTRACTOR(S WHO MAY PERFORM WORK ON THIS PROJECT OF THE REQUIREMENTS IN IMPLEMENTING AND MAINTAINING THESE EROSION CONTROL PLANS AND THE NATIONAL POLLUTANT DISCHARGE SYSTEM (NPDES) PERMIT REQUIREMENTS

- F. THE IMPACT OF THE CONSTRUCTION PROJECT SHALL BE A PRIORITY FOR ALL WEEKLY AND POST-STORM INSPECTIONS.
- G. STABILIZATION MEASURES SHALL BE IN PLACE AT THE CONCLUSION OF EACH WORK DAY
- H. ALL RIP-RAP SHALL BE SUFFICIENTLY CLEANED OF FINES PRIOR TO PLACING.

5. MAINTENANCE.

(I) THE CONTRACTOR SHALL MAINTAIN THE SEDIMENT AND EROSION CONTROL MEASURES IDENTIFIED ON THIS PLAN UNTIL THE SITE IS STABILIZED, ITEMS IN NEED OF REPAIR SHALL BE ADDRESSED AS SOON AS PRACTICABLE. MAINTENANCE ITEMS INCLUDE SHORE LINES AND VEGETATION THROUGHOUT THE SITE.

INSPECTIONS

A. QUALIFIED PERSONNEL (PROVIDED BY THE PERMITTEE) SHALL INSPECT DISTURBED AREAS OF THE CONSTRUCTION SITE THAT HAVE NOT BEEN FINALLY STABILIZED, STRUCTURAL CONTROL MEASURES, AND LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE AT LEAST ONCE EVERY SEVEN CALEBDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM THAT IS 0.5 INCHES OR GREATER OR EQUIVALENT SNOWFALL OULLIFIED PRESONNEL MEANS A PERSON MOWILEDGEABLE IN THE PRINCIPLES AND PRACTICE OF EROSION AND SEDIMENT CONTROLS, SUCH AS A LICENSED PROFESSIONAL ENGINEER OR OTHER KNOWLEDGEABLE PRESON WHO POSSESSES THE SKILLS TO ASSESSE COMMITTIONS AT THE CONSTRUCTION STET THAT COLD IMPACT STORM WATER QUALITY AND TO ASSESS IN SESSES COMMITTIONS AT THE CONSTRUCTION STET THAT COLD IMPACT STORM WATER QUALITY AND TO ASSESS IN SESSES IN STRUCTION ACASING CONTROL OF STORM WATER DISCHARGES FROM THE CONSTRUCTION ACTIVITIES.

B. DISTURBED AREAS AND AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION SHALL 6. DISTORBED AREAS AND AREAS SEEP FOR STORMS OF PRACEINALS THAT ARE EARLOSED TO PRECIPITATION SHA BE INSPECTED FOR EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM. BROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN SHALL BE OBSERVED TO ENSURE THAT THEY ARE OPERATING CORRECTLY. WHERE DISCHARGE LOCATIONS OR POINTS ARE ACCESSIBLE, THEY SHALL BE INSPECTED TO ASCERTAIN WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO RECEIVING WATERS. LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE SHALL BE INSPECTED FOR EVIDENCE OF OFFSITE SEDIMENT TRACKING.

C. BASED ON THE RESULTS OF THE INSPECTION, THE DESCRIPTION OF POTENTIAL POLLUTANT SOURCES IDENTIFIED IN THE PLAN IN ACCORDANCE WITH PARAGRAPH I (SITE DESCRIPTION) OF THESE HOTES AND POLLUTION PREVENTION MEASURES IDENTIFIED IN THE PLAN IN ACCORDANCE WITH PARAGRAPH 3 (CONTROLS) OF THESE NOTES SHALL BE REVISED AS APPROPRIATE AS SOON AS PRACTICABLE AFTER SUCH INSPECTION, SUCH MODIFICATIONS SHALL PROVIDE FOR TIMELY IMPLEMENTATION OF ANY CHANGES TO THE PLAN WITHIN 7 CALENDAR DAYS FOLLOWING THE INSPECTION.

D. A BEPORT SUMMARIZING THE SCOPE OF THE INSPECTION, MANKES) AND QUALIFICATIONS OF PERSONNEL MAKING THE INSPECTION, THE DATES OF THE INSPECTION, MADIO ROBSERVATIONS RELATING TO THE IMPLEMENTATION OF THE STORM WATER POLLUTION PREVENTION PLAN, AND ACTIONS TAKEN IN ACCORDANCE WITH PARAGRAPH B ABOVE SHALL BE MADE AND RETAINED AS PART OF THE STORM WATER POLLUTION PREVENTION PLAN FOR AT LEAST THREE YEARS FROM THE DATE THAT THE PERMIT COVERAGE EXPIRES OR IS TERMINATED. THE REPORT SHALL BE SIGNED BY THE PERMITTEE.

E. THE PERMITTEE SHALL COMPLETE AND SUBMIT WITHIN 5 DAYS AN "INCIDENCE OF NONCOMPLIANCE" (ION) REPORT FOR ANY VIOLATION OF THE STORM WATER POLLUTION PREVENTION PLAN OBSERVED DURING AN INSPECTION CONDUCTED, INCLUDING THOSE NOT RECURRED BY THE PLAN, SUBMISSION SHALL BE ON FORMS PROVIDED BY THE FACENCY AND INCLUDE SPECIFIC INFORMATION ON THE CAUSE OF NONCOMPLIANCE, ACTIONS WHICH WERE TAKEN TO PREVENT ANY FURTHER CAUSES OF NONCOMPLIANCE, AND A STATEMENT DETAILING ANY ENVIRONMENTAL IMPACT WHICH MAY HAVE RESULTED FROM THE NONCOMPLIANCE.

- F. ALL REPORTS OF NONCOMPLIANCE SHALL BE SIGNED BY THE PERMITTEE
- G. REPORTS OF NONCOMPLIANCE SHALL BE MAILED TO THE AGENCY AT THE FOLLOWING ADDRESS:

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY DIVISION OF WATER POLLUTION CONTROL COMPLIANCE ASSURANCE SECTION 1021 NORTH GRAND AVENUE EAST POST DEFICE BOX 19276 SPRINGFIELD, ILLINOIS 62794-9276

NON-STORM WATER DISCHARGES.

- THE FOLLOWING SOURCES OF NON-STORMWATER MAY BE COMBINED WITH STORMWATER DISCHARGES ASSOCIATED WITH THE INDUSTRIAL ACTIVITY ADDRESSED IN THIS PLAN.

- FIRE FIGHTING ACTIVITIES
 *WATER MAIN, HYDRANT FLUSHING
 *WATERING FOR DUST CONTROL
 *IRRIGATION DRAINAGE FOR VEGETATIVE GROWTH
- WASH WATER WHERE DETERGENTS ARE NOT USED.
- "UNCONTAMINATED GROUND WATER
- B. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL NON-FIRE FIGHTING DISCHARGES FROM WATER MAINS AND PUMPS SHALL NOT BE PERMITTED TO FLOW DIRECTLY TIMES.

 NON-FIRE FIGHTING DISCHARGES FROM WATER MAINS AND PUMPS SHALL NOT BE PERMITTED TO FLOW DIRECTLY ONTO THE SOIL WITHOUT ENERGY DISSIPATERS SUFFICIENT TO REDUCE VELOCITIES TO A NON-EROSIVE RATE, ALL SITE DE-WATERING, INCLUDING PUMP DISCHARGE SHALL PASS THROUGH SEDIMENT CONTROL DEVICES PRIOR TO LEAVING THE SITE.

8. RETENTION OF RECORDS

- A THE PERMITTEE SHALL RETAIN COPIES OF STORM WATER POLITITION PREVENTION PLANS AND ALL REPORTS AND NOTICES REQUIRED BY THIS PERMIT, AND RECORDS OF ALL DATA USED TO COMPLETE THE NOTICE OF INTENT
 TO BE COVERED BY THIS PERMIT, FOR A PERIODS OF AT LEAST THREE YEARS FROM THE DATE THAT THE PERMIT COVERAGE EXPIRES OR IS TERMINATED. THIS PERIOD MAY BE EXTENDED BY REQUEST OF THE AGENC
- B. THE PERMITTEE SHALL RETAIN A COPY OF THE STORM WATER POLLUTION PREVENTION PLAN REQUIRED BY THIS PERMIT AT THE CONSTRUCTION SITE FROM THE DATE OF PROJECT INITIATION TO THE DATE OF FINAL STABILIZATION.

9. NOTICE OF TERMINATION, UPON FINAL STABILIZATION OF THE SITE THE PERMITTEE SHALL SUBMIT A COMPLETED NOTICE OF TERMINATION IN ACCORDANCE WITH NPDES PERMIT NO. ILR10.

- 10. CERTIFICATION STATEMENT, THE FOLLOWING STATEMENT SHALL BE SIGNED PRIOR TO ANY WORK AUTHORIZED BY NPDES PERMIT NO. ILR30 IS PERFORMED AT THE SITE. THE UNDERSIGNED IS RESPONSIBLE FOR IMPLEMENTATION OF ALL MEASURES IDENTIFIED ON THIS PLAN.
- I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND THE TERMS AND CONDITIONS OF THE GENERAL NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT (ILR10) THAT AUTHORIZES THE STORM WATER DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITY FROM THE CONSTRUCTION SITE IDENTIFIED AS PART OF THIS CERTIFICATION

DATED THIS	DAY OF
	
BY	
TITLE	
COMPANY	
ADDRESS	
TELEPHONE	

	·			_									
	STABILIZATION TYPE	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	ост	NOV	DEC
	PERMANENT SEEDING			+A		A'+-				-	A'+		
	DORMANT SEEDING	В		-								+B	
	TEMPORARY SEEDING			+c			-	D		-			
	SODDING			+E**									
Г	MULCHING	F											
	WULGHING												
Α	MIXED WITH PERENNIAL RYEGRASS				SPRING OATS 100 LBS/ACRE IRRIGATION NET JUNE AND JULY WHEAT OR CEREAL RYE 150 LBS/ACRE IRRIGATION NET								
A'	* NATIVE SEEDING				SS/ACRE	-		" IRRIGATION NEEDED FOR 2 TO 3 WEEKS AFTER				JK	
В	B KENTUCKY BLUEGRASS 135 LBS/ACRE					SOD STRAW MULCH 2 TONS/ACRE			APPLYING SOD				

SOIL STABILIZATION CHART

11. DEWATERING NOTES

- CONTRACTOR SHALL BE RESPONSIBLE FOR DEWATERING EXISTING FAIRGROUNDS BASIN, A DEWATERING PLAN SHALL BE PREPARED AND SUBMITTED TO OWNER AND ENGINEER FOR APPROVAL PRIOR TO STARTING ANY DEWATERING ACTIVITIES.
- DEWATERING PLAN SHALL INCLUDE PUMP SIZES, FLOW RATES, INTAKE AND DISCHARGE LOCATIONS. AND ALL SEDIMENT AND EROSION CONTROL MEASURES.
- DEWATERING ACTIVITIES SHALL FOLLOW IUM PRACTICE STANDARD 813 AND ANY LOCAL OR COUNTY
- THE FOLLOWING DE-WATERING CONTROLS SHALL BE CONSIDERED FOR DEPLOYMENT AND THE POLLOWING DEVALENING COUNTIONS SHALL BE CONSIDERED FOR DEPLOTMENT AND
 MIPLEMENTATION, WHEN THIS STUATION EXISTS (THIS LIST IS NOT EXHAUSTIVE OTHER
 PRODUCTS OR DEVICES MAY BE CONSIDERED FOR DEPLOYMENT):
 - FLOATED PUMP INTAKES/SUMP PITS
 - PRELIMINARY SEDIMENT SETTLING TANKS/COLLECTION AREAS
 - FILTER BAGS
 - SECONDARY CONTAINMENT DOWNSTREAM OF FILTER BAGS

FILTERED CLEAR WATER SHALL BE DISCHARGED ONTO A STABILIZED SURFACE THAT PREVENTS

OR SIGNIFICANTLY MINIMIZES NEW EROSION OR SEDIMENTATION AT THE PUMP DISCHARGE LOCATION(S)

<u> </u>
 5


V3 Companies 7325 Janes Avenue Woodridge, IL 60517 630.724.9200 phone 630.724.9202 (ax

REVISED OT SCALE -CHECKED REVISED DATE REVISED

DUPAGE COUNTY CAMPUS STORMWATER POND IMPROVEMENTS MINIFIELD / WHEATON ENGINEERING PLANS ILLINOIS

EROSION CONTROL AND SWPPP NOTES SHEET 1 OF 1 SHEETS STA.


COUNTY 21 CONTRACT NO. 211350





LOCATION	RR SIZE	La	W1	W2	D
FES-10	RR-3	10'	3'	11'	15"
EX. N. DITCH (EAST POND)	RR-4	35'	20'	35'	20"
EX. S. 36" PIPE (EAST POND)	RR-4	24'	9.	27'	20"
EX W. 42" PIPE (EAST POND)	RR-4	22'	11'	26'	20"

ROCK PROTECTION AT PIPE OUTLET, N.T.S.


TABLE OF VALUES FOR ROCK PROTECTION








CEB **DUPAGE COUNTY CAMPUS** COUNTY CMR REVISED **EROSION CONTROL DETAILS** STORMWATER POND IMPROVEMENTS CHECKED JNHM REVISED REVISED INFIELD / WHEATON ENGINEERING PLANS PROJECT NO. 211350 REVISED ILLINOIS SCALE: N.T.S. SHEET 1 OF 2 SHEETS STA.





FLOATING SILT CURTAIN - TYPICAL LAYOUT HODRING CABLE - ATTACHED TO LOASLINE BETWEEN PANELS

TYPICAL COMPONENTS / ANCHORAGE SYSTEM

-ANCHOR FLOATING SILT

FIGATING STATE BARRIER SKIRT LENGTH TO BE APPROX TEN FERCENT LONGER THAN MATTER REPORT

BALLIST CHAIN


TYPICALPLAN VIEW

Maximum flow for waterbooky shall be less than 5fps.

Isolated work area shall not exceed more than 1/3 stream width. Silt curtain shall be placed parallel to stream flow.


SOLATED VORK AREA


SECURE SILT CURTAIN _____



TEMPORARY TOPSOIL STOCKPILE

DETAIL 3





REVISED REVISED CHECKED JNHM REVISED LOT DATE = 5/1/2023 DATE REVISED


DUPAGE COUNTY CAMPUS STORMWATER POND IMPROVEMENTS WINFIELD / WHEATON ENGINEERING PLANS ILLINOIS SCALE: N.T.S.


IUM-617A

IL-650 SHEET 1 OF 1 DATE 8-11-94

EROSION CONTROL DETAILS SHEET 2 OF 2 SHEETS STA.

COUNTY TOTAL SHEET NO. DUPAGE 21 16 CONTRACT NO. 19172.03






DRAWN REVISED REVISED CHECKED REVISED REVISED DATE REVISED


DUPAGE COUNTY CAMPUS STORMWATER POND IMPROVEMENTS INFIELD / WHEATON ENGINEERING PLANS


CONSTRUCTION DETAILS ILLINOIS SCALE: N.T.S. SHEET 1 OF 5 SHEETS STA.


COUNTY TOTAL SHEET NO.

DUPAGE 21 17 PROJECT NO. 211350









Y	V3 C 7325 Woo 630. 630. www


USER NAME = cray	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE =	CHECKED -	REVISED -
PLOT DATE = 5/1/2023	DATE -	REVISED -


DUPAGE COUNTY CAMPUS	
STORMWATER POND IMPROVEMENTS	
WINFIELD / WHEATON ENGINEERING PLANS ILLINOIS	SCALE: N.

REVISED REVISED

CONSTRUCTION DETAILS	D	
N.T.S. SHEET 2 OF 5 SHEETS STA TO STA	CON	SHEETS STA TO STA CON

MODEL: Default FILE NAME: N:2021/211350/2





LIGHT POLE FOUNDATION, 24" DIAMETER, SPECIAL

	USER NAME = cray	DESIGNED -	REVISED	REVISED -
17		DRAWN -	REVISED -	REVISED -
10	PLOT SCALE -	CHECKED - JNHM	REVISED -	REVISED -
	PLOT DATE = 5/1/2023	DATE	REVISED -	REVISED -


DUPAGE COUNTY CAMPUS	l				
STORMWATER POND IMPROVEMENTS					
ENGINEEDING DI ANG					
FIELD / WHEATON ENGINEERING PLANS	П				


CONSTRUCTION DETAILS								
SCALE: N.T.5	SHEET	3	OF	5	SHEETS	5TA	TO STA.	


 COUNTY
 TOTAL SHEETS NO.

 DUPAGE
 21
 19

 CONTRACT NO. 211350









Y	V3 Companies 7325 Janes Avenue Woodridge, IL 60517 630-724-9200 phone 630-724-9202 fax www.v3co.com


DUPAGE COUNTY CAMPUS STORMWATER POND IMPROVEMENTS WINGELD/WHEATON ENGINEERING PLANS

	(CON	IST	?U (CTION	DETAILS	
ALE: ALE	CHEET	- 4	OF	- 6	CHECTE	ETA	

MODEL: Default FILE MAME: NE/2021/211350







V3 Cemperation 725 Janes Aversure Winds County Campus STORMWATER POND IMPROVEMENTS STORMWATER POND IMPR

promittable affecting freeding affection of the contract of th

FILE NAME: N:2021/21135